

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 NR. 3 E.

Chippewa COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 32-33 on south boundary of twp.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 8" Cedar N 87° W 29 links
Marked "S 32 NBT"

6" Cedar N 5° E 30 links
Marked "S 33 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Corner from one cedar B.T. bearing N 15° W 17 links, down but in fair condition. Found wood post in place.

Found 7" cedar (down) bearing S 73° W 22 links. This tree scribed "S6", very old. Believed marked in error, should be "S 5".

NOTE: Closing corner between Sec.'s 4-5 T42N R3E lies 55 links east.

Corner found by Forestry Division Survey Crew.

SURVEYORS SEAL

SIGNED

Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE 5/3/57