

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
 CHIPPEWA COUNTY
 STATE OF MICHIGAN

94 JUL 22 AM 11:08

J. Roger Malott
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in
Chippewa
 (County)

Located In: _____ Corner Code # _____

- | | | |
|-------------------------|--------------------------|------------|
| 1. Public Land Survey | T _____ R _____ | |
| 1/4 Corner | T <u>43N</u> R <u>1E</u> | <u>A-4</u> |
| 1/4 Corner | T <u>43N</u> R <u>1E</u> | <u>A-2</u> |
| | T _____ R _____ | |
| 2. Property Controlling | S _____ T _____ R _____ | |
| in Section | S _____ T _____ R _____ | |
| 3. Miscellaneous | S _____ T _____ R _____ | |
| Property in Sec. | S _____ T _____ R _____ | |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters, in a field survey on OCTOBER 5, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3; 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- (A-4) From 1986 Mackinac Co. LCRC, L.C, P.151: "Set 1/4" re-rod with L.S. cap #29251, 1' West of centerline of M-129. R/W Marker East 76.02', SE House Corner S55W 137.05' Power Pole, N40W 103.19'
 1992: Neil Hill reset 1/4" iron with cap #27447, (L.7, P.358) East 75.93' Nail Top R/W Marker, West 72.64' Nail Top R/W Marker, S55W 136.95' SE Corner House, N40W 103.10 MDOT Tag in PP, N40W 103.16' PK Nail in PP
- (A-2) 1982 Chippewa Co. LCRC, L.5, P.227: Re-set corner with iron & cap #27450 and wit.
 1992: Neil Hill reset 1/4" iron with cap #27447, (Liber 7, Page 358). N31E 127.23' MDOT Tag in PP, East 76.11 Top C/L Conc. R/W Marker leaning South, S45W 95.77' MDOT Tag PP# E80 N27W 140.88' MDOT Tag in PP# E 81
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- (A-4) Found corner and all accessories as recorded in Liber 7, Page 358 of the Chippewa County Records. Accepted corner position as found.
- (A-2) Found corner and all accessories as recorded in Liber 7, Page 358 of the Chippewa County Records. Accepted corner position as found.

**SURVEY &
 REMONUMENTATION**

JUL 26 1994

COMMISSION



- Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(A-4) 1/4" Rod & cap #27447 in monument box (A-2) 1/4" Rod & cap #27447 in monument box

WITNESSES

East	75.93'	Nail Top R/W Marker
West	72.64'	Nail Top R/W Marker
S 55 W	136.95'	SE Corner House
N 40 W	103.10	MDOT Tag in PP
N 40 W	103.16'	PK Nail in PP

WITNESSES

N 31 E	127.23'	MDOT Tag in PP
East	76.11	Top C/L Conc. R/W Marker leaning South
S 45 W	95.77'	MDOT Tag PP# E 80
N 27 W	140.88'	MDOT Tag in PP# E 81

Recorded by Keith R. Waters Date 7-22-94

Surveyor's Michigan License No. 33142

NOTE: Bearings are compass bearings corrected for declination.
 Distances are to a nail in side of witness objects unless noted.