

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa
(County)

Located In: _____ Corner Code ## _____

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

94 JUL 22 AM 11:11

J. Roger Marshall
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey T _____ R _____
 1/4 Corner T 43N R 1E A-6
 Section Corner T 43N R 1E A-5
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Keith R. Waters, in a field survey on OCTOBER 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-6) From N. Hill Notes, 5-7-91: Set 1/4 Corner on line between section corners 2641.74' North and 2629.74' South. Location Determined by fence line West and brushed opening East. Preserved location prior to road construction with natural witnesses.

1992: Neil Hill reset 1/2" iron with cap #27447 (L.7, P.357) N70W 72.82' Power Pole, West 75.67' Corner Fence Post, S65W 106.43' Southerly Gate Post, East 75.64' Top Center R/W Marker, S75E 133.46' 8" Tamarack, North 2641.74' Sec. Corner, South 2629.74' Sec. Corner

(A-5) From Chippewa County ICRC, L.2, P.253 (1960 Survey): 1" Iron pin in monument box. From MDOT Notes, 4-26-91: 1" pin witnessed prior to road construction.

1992: Neil Hill found and accepted 1" pin (L.7, P.357). N40W 79.94' Power Pole, S75E 74.60' Guy Pole, S60W 84.88' Power Pole, S50E 116.11' 13" Elm, South 2641.74' 1/4 Corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-6) Found corner and accessories as recorded in Liber 7, Page 357 of the Chippewa County Records. Accepted corner position as found.

(A-5) Found corner and accessories as recorded in Liber 7, Page 357 of the Chippewa County Records. Accepted corner position as found.

SURVEY &
REMONUMENTATION

JUL 26 1994

COMMISSION



- Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-6) 1/2" iron rod & cap #27447
in monument box

(A-5) 1" pin in monument box at M-48
East and M-129

WITNESSES

WITNESSES

| | | |
|--------|----------|-----------------------|
| N 70 W | 72.82' | Power Pole |
| West | 75.67' | Corner Fence Post |
| S 65 W | 106.43' | Southerly Gate Post |
| East | 75.64' | Top Center R/W Marker |
| S 75 E | 133.46' | 8" Tamarack |
| North | 2641.74' | Section Corner |
| South | 2629.74' | Section Corner |

| | | |
|--------|----------|------------|
| N 40 W | 79.94' | Power Pole |
| S 75 E | 74.60' | Guy Pole |
| S 60 W | 84.88' | Power Pole |
| S 50 E | 116.11' | 13" Elm |
| South | 2641.74' | 1/4 Corner |

Recorded by Keith R. Waters

Date 7-22-94

Surveyor's Michigan License No. 33142

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.