

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

94 JUL 22 AM 11:11

*J. Roger Madell*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Chippewa

(County)

Located In:

Corner Code #

- 1. Public Land Survey
  - T \_\_\_\_\_ R \_\_\_\_\_
  - 1/4 Corner T 43N R 1E A-10
  - Section Corner T 43N R 1E A-9
  - T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section
  - S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
  - S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec.
  - S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
  - S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Keith R. Waters in a field survey on OCTOBER 2, 19 93.  
Do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

(A-10) From 1987 Mackinac Co. LCRC, L.C., P.301 & Chippewa Co. LCRC L.7, P.29: Found 1/2" rod 4" below bituminous surface.

1992: Neil Hill found boat spike and accepted (L.7, P.355). S50E 80.96' Power Pole N85W 72.37' Power Pole, S85E 71.88' Concrete R/W Marker, N80W 77.52' Conc R/W Marker N40E 115.70' 4" Cedar

(A-9) From 1987 Chippewa County LCRC, L.7, P.29: 1" square bolt in monument box under bituminous surface and witnessed.

1992: Neil Hill found 1" square head bolt and accepted (L.7, P.355). S80W 51.14' 8" Poplar, S60E 79.46' Power Pole, N70E 72.94' Fence Post, S55E 55.64' 4" Apple, N60W 35.82' Chis. "+" South end concrete culvert end section.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-10) Found corner and accessories as recorded in Liber 7, Page 355 of the Chippewa County Records. Accepted corner position as found.

(A-9) Found corner and accessories as recorded in Liber 7, Page 355 of the Chippewa County Records. Accepted corner position as found.

SURVEY &  
REMONUMENTATION

JUL 26 1994

COMMISSION



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-10) Boat Spike in monument box.

WITNESSES

- S 50 E 80.96' Power Pole
- N 85 W 72.37' Power Pole
- S 85 E 71.88' Concrete R/W Marker
- N 80 W 77.52' Concrete R/W Marker
- N 40 E 115.70' 4" Cedar

(A-9) 1" Square Head bolt in monument box.

WITNESSES

- S 80 W 51.14' 8" Poplar
- S 60 E 79.46' Power Pole
- N 70 E 72.94' Fence Post
- S 55 E 55.64' 4" Apple
- N 60 W 35.82' Chis. "+" South end conc culvert end section

Recorded by Keith R. Waters

Date 7-22-94

Surveyor's Michigan License No. 33142

NOTE: Bearings are compass bearings corrected for declination.  
Distances are to a nail in side of witness objects unless noted.