

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa
(County)

Located in: Corner Code #

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

94 JUL 22 AM 11:09

J. Roger Malott

REGISTER OF DEEDS
Register of Deeds Stamp & File Number

- 1. Public Land Survey
Section Corner
1/4 Corner
T ___ R ___
T 43N R 1E
T 43N R 1E
T ___ R ___
T ___ R ___
- 2. Property Controlling
In Section
S ___ T ___ R ___
S ___ T ___ R ___
- 3. Miscellaneous
Property in Sec. S ___ T ___ R ___
S ___ T ___ R ___
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A-11
A-12

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters, in a field survey on OCTOBER 3, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-11) From MDOT: Found boat spike in mon. box prior to road reconstruction & witnessed. 1992: Neil Hill found and accepted boat spike (L.7, P.354). S40E 104.51' MDOT Tag in PP, S60W 83.46' MDOT Tag in PP, N75W 75.63' Tag w/ End Gut Pan, N50E 41.33' Stencil "+" Top Center Conc. Hdwl.

(A-12) From MDOT: Found plastic cap #33142 prior to road reconstruction and witnessed. 1992: Neil Hill found and accepted 1/2" pin with cap #33142 (L.7, P.354). West 42.27' MDOT Tag in 4" Balsam N60W 55.06' MDOT Tag in 8" Cedar N85W 38.73' Punch Top Con. R/W Marker N75E 76.05' MDOT Tag in 3" Cedar S35E 113.27' MDOT tag in PP #E-34

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-11) Found corner and all accessories as recorded in Liber 7, Page 354 of the Chippewa County Records. Accepted corner position as found.

(A-12) Found corner and all accessories as recorded in Liber 7, Page 354 of the Chippewa County Records. Accepted corner position as found.

SURVEY &
REMONUMENTATION

JUL 26 1994

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-11) Boat Spike in Monument Box

(A-12) 1/2" Rod & Cap #33142 in Monument Box.

WITNESSES

WITNESSES

S 40 E 104.51' MDOT Tag in PP
S 60 W 83.46' MDOT Tag in PP
N 75 W 75.63' Tag w/ End Gut Pan
N 50 E 41.33' Stencil "+" Top Center Conc. Hdwl.

West 42.27' MDOT Tag in 4" Balsam
N 60 W 55.06' MDOT Tag in 8" Cedar
N 85 W 38.73' Punch Top Con. R/W Marker
N 75 E 76.05' MDOT Tag in 3" Cedar
S 35 E 113.27' MDOT tag in PP #E-34

Signed by Keith R. Waters

Date 7-22-94

Surveyor's Michigan License No. 33142

NOTE: Bearings are compass bearings corrected for declination.

Distances are to a nail in side of witness objects unless noted.