

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa

(County)

Located In:

Corner Code #/

- 1. Public Land Survey
 1/2 Corner Common: T 44N R 1W M-10
 Section Corner: T 44N R 1E A-10
 Common to: T 44N R 1W M-9
 T 44N R 1E A-9
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec. S T R

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

94 JUL 22 AM 11:10

J. Roger Malott

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters, in a field survey on OCTOBER 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M-10) From N. Hill L.L.S., 5-7-91: Corner established on fence line West & apparent property line East and on line between Section Corner 2642.15' North and 2636.70' South. 1992: Neil Hill reset 1/2" iron with cap #27447 (L.7, P.361). West 77.62' Top C/L Conc. R/W Mkr, N50W 92.91' Fence Post, East 69.20' Power Pole, S50E 96.89' C/L SW Sign Bolt, N88E 71.13' USGS BM Disk in Con, North 2642.15' Section Cor, South 2636.70' Section Cor.

(M-9) From 1986 LCRC, L.6, P.297: Fd. 1" iron in mon. box on intersection paved road C/L Accepted. 1992: Neil Hill found 3/4" iron and accepted (L.7, P.361). S42E 107.62' MDOT Tag PP PD4/PD3/19, S42E 107.71' Found PK PP PD4/PD3/19, S58W 97.91' Chis "+" Leaning Conc. Mkr, N42W 99.15' MDOT Tag PP PD4/19A, N42W 99.10' Found PK PP PD4/19A, N80E 66.06' Chis "+" E End Conc. Pan

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-10) Found corner and all accessories as recorded in Liber 7, Page 361 of the Chippewa County Records. Accepted corner position as found.

(M-9) Found corner and all accessories as recorded in Liber 7, Page 361 of the Chippewa County Records. Accepted corner position as found.

SURVEY &
REMONUMENTATION

JUL 26 1994

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-10) 1/2" rod & cap #27447 in Westerly Side of Monument Box 3' East of existing M-129 centerline

(M-9) 3/4" rod in monument box

WITNESSES		WITNESSES	
West	77.62'	Top C/L Conc. R/W Mkr	S 42 E 107.62' MDOT Tag PP PD4/PD3/19
N 50 W	92.91'	Fence Post	S 42 E 107.71' Found PK PP PD4/PD3/19
East	69.20'	Power Pole	S 58 W 97.91' Chis "+" Leaning Conc. Mkr
S 50 E	96.89'	C/L SW Sign Bolt	N 42 W 99.15' MDOT Tag PP PD4/19A
N 88 E	71.13'	USGS BM Disk in Conc.	N 42 W 99.10' Found PK PP PD4/19A
North	2642.15'	Section Corner	N 80 E 66.06' Chis "+" E End Conc. Pan
South	2636.70'	Section Corner	

Signed by Keith R. Waters

Date 7-22-94

Surveyor's Michigan License No. 33142

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.