

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa
(County)

Located In: Corner Code #/

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

94 JUL 22 AM 11:08

J. Roger Malott

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey T _____ R _____
{ T 43N R 1E A-1
- Twp. Corner Common To: { T 44N R 1E A-13
{ T 44N R 1W M-13
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Keith R. Waters, in a field survey on OCTOBER 5, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:
1982 Chippewa County ICRC Liber 5, Page 229: Found 5/8" iron in monument box,
S39E 127.69' Bldg. Corner N73E 76.65' Power Pole
N67W 52.66' Power Pole S17W 76.73' Power Pole
MDOT notes 4-29-91: Found corner and witnessed prior to road construction with hubs & natural witnesses. N73E 76.50' Power Pole N67W 52.11' Power Pole
S17W 76.54' Power Pole S70W 76.51' Power Pole

1992: Neil Hill reset 1/2" iron with cap #27447 (Liber 7, Page 359)
S39E 127.64' Wood Building Corner N73E 76.46' MDOT Tag in Power Pole
N67W 52.09' MDOT Tag in Power Pole S17W 76.53' MDOT Tag in Power Pole
S70W 76.52' MDOT Tag in Guy Pole

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found corner and all accessories as recorded in Liber 7, Page 359 of the Chippewa County Records. Accepted corner position as found.

SURVEY &
REMONUMENTATION

JUL 26 1994

COMMISSION



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner is a 1/2" iron and cap #27447 in monument box.

WITNESSES

- S 39 E 127.64' Wood Building Corner
- N 73 E 76.46' MDOT Tag in Power Pole
- N 67 W 52.09' MDOT Tag in Power Pole
- S 17 W 76.53' MDOT Tag in Power Pole
- S 70 W 76.52' MDOT Tag in Guy Pole

Signed by Keith R. Waters Date 7-22-94

Surveyor's Michigan License No. 33142

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.