

MAR 09 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 29 PM 2:47

For corners in Chippewa  
(County)

Located In: Corner Code =#

*J. Roger Melick*  
REGISTER OF DEEDS

1. Public Land Survey	T <del>44N</del> R <del>1E</del>	<u>D-13</u> Same
	T 43N R 1E	D-1 / Corner
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_


A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William L. Karr, in a field survey on December 18, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
(D-13) 1/2 Corner Common to Sections 32 & 5 (T44N-R1E)

1840: Corner established by Austin Burt for William A. Burt.  
Set 1/4 Section Post  
Tamarack 7 N10°W 10 links  
Tamarack 10 N51°E 29 links



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D-13) This corner is being re-established as part of the Chippewa County Remonumentation Program.

Found no evidence of original corner. Found a North-South fence line on the North side of the road. Did not hold fence line. Re-established corner position midway and on line between the Southeast and Southwest corners of Section 32. Corner position falls 20' West of extension of fence line to the North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D-13) Corner is a 3/4" x 24" iron with plastic "Chippewa County Remonumentation" cap. Falls 3' North of the centerline of Gogomain Road (East-West, paved). Falls 20' West of extension of fence line to the North.

Witnesses:

4" Spruce	N79°E	165.65'
Power Pole	S83°E	424.82'
Power Pole	S01°E	48.50'
3" Spruce	N73°W	110.65'



Signed by William L. Karr Date 12/23/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.  
Distances are to a nail in side of witness objects unless noted.