

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

94 JUL 22 AM 11:15

J. Roger Mullett
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey

T 44N R 1E H-5

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Larry R. Rogers, in a field survey on 23 NOVEMBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(H-5) 1/4 Corner Common to Sections 10 and 15 (T44N-R1E)

Corner established by John Mullett in 1845. Corner re-established by C.M. Cade in 1930 in a survey of Munuscong State Park. A survey by Billy D. Buckler in 1972 and recorded in Liber 1 at Page 13, notes corner but gives no description.

1987: L.R. Rogers re-established corner (Liber 7, Page 103).

"V" Notch in Guard Rail Post	N10°E	28.30'
Power Pole (PD2/21/51N)	N70°E	81.81'
20" Willow	S08°W	73.25'
Southeast corner of house foundation	S50°W	173.41'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H-5) Found corner and all accessories as recorded in Liber 7, Page 103 of the Chippewa County Records. Accepted corner position as found.

SURVEY &
REMONUMENTATION

JUL 26 1994

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H-5) Corner is a 1/2" x 18" iron with L.S. cap #29251, 6" below surface of gravel drive. Corner falls on the extension of a fence line to the East and 20'± West of centerline of North-South County Road (Riverside).

Witnesses:	"V" Notch in Guard Rail Post	N10°E	28.30'
	Power Pole (PD2/21/51N)	N70°E	81.81'
	20" Willow	S08°W	73.25'
	Southeast corner of house foundation	S50°W	173.41'

Signed by _____

Date 20 July 1994

Surveyor's Michigan License No. 29251

141-74

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.