

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 NR. 1E ..

Chippewa

COUNTY

DESCRIPTION OF CORNER Closing Corner between Sections 5-6 on north boundary of twp.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 8" Cedar S 33° E 38 links  
Marked "S 5 NBT"  
6" Cedar N 62° E 48 links  
Marked "S 52 NBT"

Dept. Marker for Section Corner 31-32, T45N R1E is  
16 links west.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED.

Replaced closing corner between 5-6 16 links east of Section Corner  
common to Sections 31-32, T45N R1E according to original field notes.  
No evidence of original witnesses.

"There is an original witness for Section Corner 31-32, T45N R1E in  
place. This corner was set in 1956."

Corner lies 1/2 ch. south of winter road.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 2/19/57  
REGISTERED LAND SURVEYOR