

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 NR. 1 E . . .

Chippewa COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 8-17

DESCRIPTION OF CORNER MONUMENT 1" pipe with brass cap

WITNESSES TO CORNER 10" Tamarack S 24° E 38 links
Marked "1/4 S NBT"

9" Tamarack S 30° W 35 links
Marked "1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established 1/4 corner by proportionate measure E. & W. and on E. & W. road as cleared by County in 1930's. No evidence of original witnesses. Used measurement from meridian road 1 1/2 miles west and fence corner 1 mile east. Placed 1/4 corner in old road bed. Corner extends 6" above ground. Placed cedar post 4' north of corner.

SURVEYORS SEAL

SIGNED Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 2/27/57