

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 NR. 1 E.

Chippewa COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 8-9-16-17

DESCRIPTION OF CORNER MONUMENT 1" pipe with brass cap

WITNESSES TO CORNER 10" Tamarack S 38° W 19 1/2 links  
Marked "S 17 NBT"  
9" Tamarack N 24° W 33 links  
Marked "S 8 NBT"  
7" Tamarack N 46° E 40 links  
Marked "S 9 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established Section Corner by proportionate measure E & W and on E & W road as cleared by County Road Commission in 1930's.

No evidence of original witnesses.

Used measurement from meridian road 2 miles west and fence corner 1/2 mile east. Placed Corner in center of old road. Corner extends 6" above ground. Placed cedar post 4' north of corner.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 2/27/57  
REGISTERED LAND SURVEYOR