

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T.44.. NR..1 East

..... Chippewa COUNTY

DESCRIPTION OF CORNER 1/4 corner between sections 5 - 8.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 7-29-58

9" cedar N 47°, W 3 links. Marked "SMBT"

7" cedar N 60°, E 37 links. Marked "SMBT"

8" cedar S 60°, W 13 links. Marked "SMBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. Replaced corner from two cedar bearing trees, bearing N 12°, W 3 links and S 8°, E 2 links. Both stumps in poor condition. Chopped out overgrowth and scribe marks are plain. Position fits stream 1 chain west. Corner found and witnessed with W. Lehman, District Forester.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 6-18-59
REGISTERED LAND SURVEYOR