

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Chippewa COUNTY


T 44N R 1E

DESCRIPTION OF CORNER Sec. Cor. common to Secs 14-15-22-23

CORNER MONUMENT 4" x 48" pipe filled with concrete, buried in center of N-S road.  
Placed a 5/8" x 36" re-rod at corner.

DATE MONUMENT PLACED AND WITNESSED 5/4/72

WITNESSES TO CORNER..... 16" Cedar (S 15 NBT) N74°N 34.6'



17" Cedar (S 14 NBT) N85°E 32.0'

Set Cedar Post, 10' East of Corner.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-witnessed as set by C.M. Cade, C.E. in 1930. Found 4" iron pipe, buried 20" below road surface. Found remains of three witnesses marked by Cade, which agree with one exception; A green Cedar now 18" bearing N86°E is 61.3' distant from corner. Record indicates 11.0'. Road apparently built on the Sec. Line since the 1930 Survey.

SURVEYOR'S SEAL

SIGNED

*Billy D. Buckler*

Billy D. Buckler

REGISTERED LAND SURVEYOR

DATE

6/20/72

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68