

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Chippewa COUNTY


T 44N R 1E

DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 14-15

CORNER MONUMENT 4" x 48" pipe, filled with concrete, buried in West edge of road.

DATE MONUMENT PLACED AND WITNESSED 5/4/72

WITNESSES TO CORNER..... 8" Tamarack (¼S NBT) N36°E 73.7'



15" Soft Maple (¼S NBT) S79°N 30.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from witnesses recorded by C.M. Cade, C.E. in 1930. Found the 4" pipe laying beside road, apparently removed during road construction. Found what appears to be an original bearing tree, a green Tamarack, now 18" in Diameter, bearing N68½°E, 71.7'. Large open face with scribe marks evident. Found remains of two witnesses by Cade; an aspen and a balsam, both dead. The distance (2657.3') South to Sec. Cor. agrees with Cades distance.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler

DATE

6/20/72

DISTRIBUTION:

REGISTERED LAND SURVEYOR

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68