

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**  
 Chippewa Co. Two Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. S. R. <u>1</u> E. <u>X</u>	<u>1-3, 1-1</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 6/20 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- 1-3 Sec. Cor. 2-3-10-11, originally set by John Mullett, D.S. in 1845.  
 Bearings were:  
 Cedar 8"  $S66^{\circ}E$  13 lks. and Cedar 12"  $S54^{\circ}W$  21 lks.
  - 1-1 Sec. Cor. 2-3, of North Emory, of Township, set by John Mullett, D.S. in 1845.  
 bearings were:  
 Hemlock 12"  $S44^{\circ}E$  10 lks. and Hemlock 12"  $S40^{\circ}W$  37 lks.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- 1-3 Marker Corner as set by C.K. Cade in 1930, with a witness monument, East, 33.0' and a 12" Spruce,  $S58^{\circ}W$ , 63.3'.
  - 1-4 Found corner as set by C.K. Cade in 1930. Found wit. monument, South, 33.0' Found 1 1/4" pipe and wood post, West, 23.1' This is the Sec. Cor. for Secs' 34-35, T45N R1E.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- 1-3 Drove 2" re-rod below road surface, at corner.  
 Bearings:  
 Monument, East, 33.0' and 12" Spruce,  $S58^{\circ}W$ , 63.3'
  - 1-1 Drove 1" pipe below road surface, at corner.  
 New Bearings:  
 14" spruce,  $S21^{\circ}E$ , 38.8'
- NOTE:**  
 Corner lies 23.1' East of Sec. Cor. 34-35, T45N R1E. and marks Secs' 2-3, T44N R1E only.

SIGNED BY Billy D. Buckler DATE 6/27/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:  
 SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)