

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Chippewa

(County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>16</u> T <u>44N</u> R <u>1E</u>	<u>8</u>
	S <u>16</u> T <u>44N</u> R <u>1E</u>	<u>C-N-SW 1/64</u>
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Feb 23 1999

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(C-N-SW 1/64) Also known as the Southeast corner of the North 1/2 of the Northwest 1/4 of the Southwest 1/4 of Section 16. Corner not established in the original survey. Found no subsequent record.  
 (8-Sec. 16) West 1/16 corner of Section 16. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-N-SW 1/64) Established the corner midway and on a straight line between 1/16 Corner #8 655.47' north and unmonumented 1/16 corner #11 655.47' south. At the position for the corner I placed a 1" IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet stamped "S16 C-N-SW 1/64".  
 (8-Sec. 16) Established the corner midway and on a straight line between Quarter corner 1312.95' west and Center of Section 1312.95' east. At the position for the corner I placed a 1" IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-N-SW 1/64) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following:	(8) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following:
14" Tamarack N86W 41.05' "1/64 BT"	12" Tamarack S05W 25.9' "W1/16 BT"
12" Tamarack N68W 44.4' do	14" Tamarack N72W 16.0' do
10" Tamarack N37E 35.65' do	6" W. Birch S71W 22.0' do
8" Tamarack S89E 19.8' do	3" W. Birch N77E 31.55' do
Bearings are magnetic. Distances to nail w/tag. Placed 4" squared and scribed cedar post adjacent.	Bearings are magnetic. Distances to nail w/tag. Placed 4" squared and scribed cedar post adjacent.



Signed by Stephan J. Szyszkoski Date 2/24/00  
 Surveyor's Michigan License No. 33986