

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code F6

1. Public Land Survey	T <u>44N</u> R <u>1E</u>	<u>F6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>16</u> T <u>44N</u> R <u>1E</u>	<u>10</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

10 Jul 13 1999
 F6 Feb 23 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		●		15		14		13		
7					●								
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(F6) Center of Section 16. Corner not established in the original survey. County Surveyor F.H. Brown did some work in Section 16 in 1912 and 1916 but his notes do not shown any monumentation at this position.
 (10-Sec. 16) South 1/16 corner between Sections 16-17. Corner not established in the original survey. County surveyor F.H. Brown did some work in Section 16 in 1912 and 1915 but I found no record of establishment of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F6) Found no acceptable evidence of prior monumentation. Established the corner at the intersection of straight lines connecting opposite quarter corners. At the position for the corner I placed a 1" IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner monumented, a fenceline intersection with fences leading east, west, and north, bears N45E, 35' distant.
 (10-Sec. 16) Established the corner midway and on a line of mean true bearing between Section corner 1309.36' south and Quarter corner 1309.36' north. At the position for the corner, which falls about 1.5' east of the center of a N-S trail road, I buried a 1" ID iron pipe capped with a yellow plastic cap stamped "MICH DNR PS 33986".

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F6) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: 3" Aspen N63W 21.2' "CS BT" 10" Aspen N33W 40.6' do fence post N60E 44.75' fence post N06E 27.2' Bearings are magnetic. Distances to nail w/tag. Placed sq'd and scribed cedar post adjacent.	(10) Set 1" pipe w/plastic MDNR cap. Blazed, scribed, and set measuring nails in the following: 4" Elm S28E 23.35' "S1/16 BT" 5" Balsam N45W 36.6' do 8" Ash S83W 23.5' do fence post N70E 33.0' Bearings are magnetic. Distances are to nail w/tag.
--	---



Signed by Stephan J. Szyszkoski Date 2/24/00
 33986