

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey	T 44N R 1E	I8
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Nov 29 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 19__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(I8) Quarter corner common to Sections 22-23. 1845 - Established by John Mullett, Deputy Surveyor: North between Secs 22 & 23 ...40.00 Set qr. section post. Cedar 10 N35E 10 links, Spruce 10 S32W 8 links. ...80.00 Set post corner secs. 14,15,22 & 23. 1894 - Notes by Co. Surveyor F.H.Brown state "There are no original government corners on this section". Brown shows distance north = 2626' and south = 2627' to adjacent Section corners. He gives reference to this corner: Cedar 6 N64 1/2E 51, Cedar 8 S79W 64.5. 1930 - C.M. Cade CE, for the Michigan Dept. of Conservation, found old stake and placed a standard monument. Cade shows the corner S0 deg. 14'W 2655.9' from I7 and N0 deg. 12'E 2655.9' from I9 and made the following witnesses: 6" Cedar S84W 44.4', 8" Cedar N60W 620', 5" Cedar N56E 39.3', 6" Cedar S71E 33.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I8) Recovered the 1930 monument, a 4" dia. concrete-filled iron pipe with brass cap in good condition and at record bearing and distance from the 4 1930 witness trees. The Cedars SW, NW, and NE are in good condition with old blazes. The Cedar SE is standing dead. True bearings to adjacent Section corners were found to be N 0 deg. 23' 02" E 2655.39' to I7 and S 0 deg. 22' 49" W 2656.24' to I9. Could not reconcile the Cade and Brown distances but I note that they are both substantially proportionate to the 1845 record. The Cedar witnesses given by Brown were not identified. Accepted the monument as the best available evidence of the position of the original corner. An old grown-in trail intersection with trails leading N and W is 20' west of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I8) Found 4" conc-filled pipe with brass cap. Set measuring nails in:
 6" Cedar S15W 10.4' mrkd "1/4S NBT"
 6" Cedar S24E 18.9' do
 5" Cedar N80E 11.35' do
 6" Tamarack N68W 14.6' do
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 1/9/07

For the Michigan Department of Natural Resources