

**SURVEY & REMONUMENTATION**

CHIPPEWA COUNTY REMONUMENTATION CORNER

APR 26 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **CHIPPEWA** COMMISSION

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>1W</u>	C-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

\$ 7.00 LAND CORNER  
\$ 2.00 MSSR  
24 OCT 94 3:44 P.M. RECEIPT# 831  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Keith R. Waters in a field survey on September 29, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-1 Corner Common to Sections 5 & 6, on North Boundary of T44N, R1W.  
(Closing Corner on Township Line)

Original ties to post: Hemlock 18, S45°E 46 links  
Fir 10, S75°W 17 links

Found no evidence of subsequent restoration of corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1 (T44N, R1W)  
This corner is being re-established as part of the Chippewa County Remonumentation Program.  
Found no evidence of corner. Re-established corner on township line at record G.L.O. distance (16.50 feet) east of standard section corner to Sections 31 & 32, T45N, R1W. Corner falls in a paved area on the east side of the north-south runway of the Chippewa County International Airport, on the north side of an east-west taxiway.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 (T44N, R1W)  
Corner is a 3/4" rebar with a plastic Chippewa County Remonumentation cap on the east side of north-south runway, on the north side of an east-west taxiway. Witnesses:  
PK nail in asphalt, N26°W 41.52' N.W. corner of 10" x 54" sign (B1-34-16)  
PK nail in asphalt, N85°W 39.84' on south side of taxiway, S74°E 194.74'  
PK nail in asphalt, S25°E 17.53' N.E. corner of 10" x 32" sign (B1) on east side of runway, S52°W 91.90'

Note: Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters  
Surveyor's Michigan License No. 33142

Date 10-18-94

