

SURVEY & REMONUMENTATION

APR 26 1995

CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|-------------------------|------------|--|
| 1. Public Land Survey | <u>T44N R 1W</u> | <u>D-1</u> | |
| | T _____ R _____ | _____ | |
| | T _____ R _____ | _____ | |
| | T _____ R _____ | _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ | |
| | S _____ T _____ R _____ | _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ | |
| | S _____ T _____ R _____ | _____ | |

\$ 7.00 LAND CORNER
\$ 2.00 MSSR
24 OCT 94 3:44 P.M. RECEIPT# 831
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SPARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters in a field survey on June 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1 North 1/4 Corner of Section 5, T44N, R1W

Corner was not set in the original survey. Found no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 (T44N, R1W)

This corner is being established as part of the Chippewa County Remonumentation Program.

Established corner on township line midway between closing corners at northwest and northeast corners of Section 5, T44N, R1W. Corner falls 14.85 feet east of a concrete monument at the south 1/4 corner of Section 32, T45N, R1W. Corner is approximately 80 feet east of an old north-south dirt road.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 (T44N, R1W)

Corner is a 3/4" x 24" rebar with 3 1/4" aluminum Chippewa County Remonumentation cap approximately 80' east of an old north-south dirt road. Witnesses:

- 20" Jack Pine, N38°W 89.45'
- 7" White Pine, N82°W 50.82'
- 5" White Pine, S71°W 49.22'
- 6" White Pine, S56°W 56.23'
- Concrete Monument (S 1/4 Corner of Section 32), WEST 14.85'

Note: Distances are to a nail and tag in the side of the witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination

Signed by Keith R. Waters Date 10-18-94

Surveyor's Michigan License No. 33142

