

**SURVEY &
REMONUMENTATION**

CHIPPEWA COUNTY REMONUMENTATION CORNER

APR 26 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
Chippewa
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------|-------|
| 1. Public Land Survey | T <u>44N</u> R <u>1W</u> | E-1 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

\$ 7.00 LAND CORNER
\$ 2.00 MSSR
24 OCT 94 3:45 P.M. RECEIPT# 831
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Keith R. Waters in a field survey on June 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1 Corner Common to Sections 4 & 5, on North Boundary of T44N, R1W.
(Closing Corner on Township Line).

Original notes indicate a Y. Pine 18 for 1/4 Section corner.

Found no evidence of subsequent restoration of corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1 (T44N, R1W)
This corner is being re-established as part of the Chippewa County Remonumentation Program.
Found no evidence of corner. Re-established corner on township line 13.20 feet east of standard corner to Sections 32 & 33, T45N, R1W, according to original G.L.O. notes. Corner falls approximately 230 feet north of an east-west 2-track road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 (T44N, R1W)
Corner is a 3/4" x 24" rebar with 3 1/4" aluminum Chippewa County Remonumentation cap approximately 230 north of an east-west 2-track road. Witnesses:

- 12" White Pine, S77°W 23.44'
- 8" Jack Pine, S49°W 31.92'
- 10" White Pine, N34°W 31.04'
- 12" White Pine, S81°E 22.11'
- Concrete Monument (Standard Corner), WEST 13.20'

Note: Distances are to a nail and tag in the side of the witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 10-18-94

