

**SURVEY & REMONUMENTATION**

APR 26 1995

CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Chippewa

(County)	Located In:	Corner Code #
1. Public Land Survey	T 44N R 1W	J-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

\$ 7.00 LAND CORNER  
\$ 2.00 MSSR  
5 DEC 94 12:33 P.M. RECEIPT# 1520  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS  
**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters in a field survey on November 8, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

J-1 North 1/4 Corner of Section 2, T44N, R1W

Corner was not set in the original survey.

Found no evidence of subsequent establishment of this corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 (T44N, R1W)

This corner is being established as part of the Chippewa County Remonumentation Program.

Found no evidence of corner. Established corner on township line mid-way between closing corner common to Sections 2 & 3, T44N, R1W to the west and closing corner common to Sections 1 & 2, T44N, R1W to the east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 (T44N, R1W)

Corner is a 3/4" x 24" rebar with 3/4" aluminum Chippewa County Remonumentation cap. Witnesses:

- 10" Hemlock, NORTH 16.26'
- 14" Yellow Birch, N80°W 4.71'
- 7" Balsam Fir, S12°W 12.53'
- Twin 14" Red Maple, S71°W 32.70'
- 3/4" Rebar w/aluminum cap at South 1/4 Cor. Sec. 35, T45N, R1W, WEST 10.89'

Note: Distances are to a nail and tag in side of tree. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-1-94

Surveyor's Michigan License No. 33142

