

SURVEY & REMONUMENTATION

APR 26 1995

CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code #

| | | | | | |
|------------------------------------|---|-----|---|----|-----|
| 1. Public Land Survey | T | 44N | R | 1W | L-1 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

\$ 7.00 LAND CORNER
\$ 2.00 MSSR
5 DEC 94 12:32 P.M. RECEIPT# 1520
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on November 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-1 North 1/4 Corner of Section 1, T44N, R1W.

Corner was not set in the original survey.

Found no evidence of subsequent establishment of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 (T44N, R1W)

This corner is being established as part of the Chippewa County Remonumentation Program.

Found no evidence of corner. Established corner on township line mid-way between closing corner common to Sections 1 & 2, T44N, R1W to the west and the township corner to the east. Corner falls 4.29 feet east of a found 1/2" iron with cap #27450 at the South 1/4 corner of Section 36, T45N, R1W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 (T44N, R1W)

Corner is a 3/4" x 24" rebar with 3 1/4" aluminum Chippewa County Remonumentation cap. Witnesses:

12" White Birch, N14°E 14.76'

Twin 12" Cedar, EAST 14.36'

12" Cedar S42°E 25.46'

12" White Birch, S67°W 23.54'

1/2" Iron w/cap #27450 @ South 1/4

Cor. Sec. 36, T45N, R1W, WEST 4.29'

Note: Distances are to a nail and tag in the side of the tree. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |



Signed by Keith R. Waters

Date 12-1-94

Surveyor's Michigan License No. 33142

