

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

94 JUL 22 AM 11:07

*J. Roger Malott*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in  
Chippewa

(County)

Located In:

Corner Code ##

- 1. Public Land Survey  $\frac{1}{4}$  Corner Common To:  $\left\{ \begin{array}{l} S 1, T 44N R 1W \\ S 6, T 44N R 1E \\ T \quad \quad \quad R \quad \quad \quad \\ T \quad \quad \quad R \quad \quad \quad \\ T \quad \quad \quad R \quad \quad \quad \\ S \quad \quad \quad T \quad \quad \quad R \quad \quad \quad \\ S \quad \quad \quad T \quad \quad \quad R \quad \quad \quad \\ S \quad \quad \quad T \quad \quad \quad R \quad \quad \quad \\ S \quad \quad \quad T \quad \quad \quad R \quad \quad \quad \end{array} \right.$  M-2  
A-2
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters, in a field survey on OCTOBER 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

(M-2) From 1982 ICRC, Liber 5, Page 216: Reset corner by Single Proportionate Measurement, using Northwest and Southwest corners of Section 6, T 44 N, R 1 E. Set  $\frac{1}{2}$ " re-rod and cap #27450. West 73.99' Pin & Cap #27450, fence line to West is North 17.0', fence line to East is South 4.5'.  
 From MDOT notes, 4-30-91: Found  $\frac{1}{2}$ " rod and set temporary and natural witnesses prior to road reconstruction.  
 Neil Hill reset  $\frac{1}{2}$ " iron with cap #27447 in 1992 (Liber 7, Page 365)  
 East 74.57' MDOT Tag in Corner Fence Post West 73.94' Pin and Cap #27450  
 N 70 E 82.85' Power Pole S 25 W 134.42' Stencil "+" on Conc. Hdwl

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-2) Found corner and all accessories as recorded in Liber 7, Page 365 of the Chippewa County Records. Accepted corner position as found.

SURVEY &  
REMONUMENTATION

JUL 26 1994

COMMISSION



Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
(M-2)  $\frac{1}{2}$ " Rod and cap #27447 in monument box.

Witnesses:

East	74.57'	MDOT Tag in Corner Fence Post
West	73.94'	Pin and Cap #27450
N 70 E	82.85'	Power Pole
S 25 W	134.42'	Stencil "+" on Conc. Hdwl

Recorded by Keith R. Waters

Date 7-22-94

Surveyor's Michigan License No. 33142

NOTE: Bearings are compass bearings corrected for declination.  
Distances are to a nail in side of witness objects unless noted.