

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa
(County)

Located In:

Corner Code #

1. Public Land Survey

Section Corner
Common to :

2. Property Controlling

in Section

3. Miscellaneous

Property In Sec.

T	44N	R	1W	M-4
T	44N	R	1E	A-4
T	44N	R	1W	M-3
T	44N	R	1E	A-3
S	T	R		
S	T	R		
S	T	R		
S	T	R		

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

94 JUL 22 AM 11:07

J. Roger Matlock

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Keith R. Waters, in a field survey on OCTOBER 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M-4) From MDOT notes, 4-30-91: Found iron as set previously by N. Hill at location verified by local surveyor. Witnessed prior to road construction with temporary and natural witnesses. 1992: Neil Hill reset 1/2" iron with cap #27447 (Liber 7, Page 364)
N60W 63.85' 6" Black Ash, N80W 54.11 5" Black Ash, N50E 55.51' 6" Balsam,
S80E 46.86' 10" Maple Stump, S55E 53.57' 6" Balsam

(M-3) From 1982 LCRC, Liber 5, Page 217: Found 1" pin in monument box 1' East of M-129 centerline. Accepted as found. N67E 94.42' 14" Yellow Birch, N66W 67.63' 6" White Spruce
1992: Neil Hill found & accepted 1" iron pin. (Liber 7, Page 364)
N67E 94.02' MDOT Tag Top 14" Y. Birch Stump N66W 67.57' MDOT Tag in 8" Spruce
S60E 74.26' MDOT Tag in Power Pole S60W 127.54' NE Corner Wood Porch

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-4) Found corner and all accessories as recorded in Liber 7, Page 364 of the Chippewa County records. Accepted corner position as found.

(M-3) Found corner and all accessories as recorded in Liber 7, Page 364 of the Chippewa County Records. Accepted corner position as found.

SURVEY &
REMONUMENTATION

JUL 26 1994

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-4) 1/2" iron rod & cap #27447 in (M-3) 1" pin in monument box.

Monument Box
WITNESSES

WITNESSES

N 60 W	63.85'	6" Black Ash
N 80 W	54.11	5" Black Ash
N 50 E	55.51'	6" Balsam
S 80 E	46.86'	10" Maple Stump
S 55 E	53.57'	6" Balsam

N 67 E	94.02'	MDOT Tag Top 14" Y. Birch Stump
N 66 W	67.57'	MDOT Tag in 8" Spruce
S 60 E	74.26'	MDOT Tag in Power Pole
S 60 W	127.54'	Northeast Corner Wood Porch

Signed by Keith R. Waters

Date 7-22-94

Surveyor's Michigan License No. 33142

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.