

5

5

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Chippewa (County)

Located In: Corner Code ##

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

94 JUL 22 AM 11:09

J. Roger Marshall
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey 1/4 Corner Common to: Section Corner Common to:
2. Property Controlling in Section
3. Miscellaneous Property in Sec.

4. Lot No. Recorded Plat
5. Private Claims

I, Keith R. Waters, in a field survey on OCTOBER 3, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(M-6) From 1988 LCRC L.7, P.094: Re-established corner midway and on line between the Northwest and Southwest corners of Section 18.
1992: Neil Hill reset 1/2" iron with cap #27447 (L.7, P.363). N15W 160.51' Fd Nail E. Side 10" Birch, N32E 115.00' Fd Nail E. Side 14" Spruce, East 74.76' MDOT Tag in Power Pole, S66W 147.47' NE Corner of Concrete Wall in Cemetery.

(M-5) From 1980 LCRC, L.5, P.002: Found 3/4" iron in monument box 2' West of M-129.
1992: Neil Hill found and used 3/4" iron (L.7, P.363). N20E 186.32' Tag #27450 in Power Pole, S78W 185.98' MDOT Tag in 12" Spruce, S85E 97.44' MDOT Tag Twin 7" Poplar, N 28 W 67.53' Stencil "+" on con. hdwl.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(M-6) Found corner and all accessories as recorded in Liber 7, Page 363 of the Chippewa County Records. Accepted corner position as found.

(M-5) Found corner and all accessories as recorded in Liber 7, Page 363 of the Chippewa County Records. Accepted corner position as found.

SURVEY & REMONUMENTATION

JUL 26 1994

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.
(M-6) 1/2" rod & cap #27447 in mon. box
(M-5) 3/4" iron in monument box at M-129 and 20 Mile Road.

WITNESSES

WITNESSES

- N 15 W 160.51' Fd Nail E. Side 10" Birch
N 32 E 115.00' Fd Nail E. Side 14" Spruce
East 74.76' MDOT Tag in Power Pole
S 66 W 147.47' NE Corner of Concrete Wall in Cemetery
N 20 E 186.32' Tag #27450 in Power Pole
S 78 W 185.98' MDOT Tag in 12" Spruce
S 85 E 97.44' MDOT Tag Twin 7" Poplar
N 28 W 67.53' Stencil "+" on con. hdwl

igned by Keith R. Waters

Date 7-22-94

33142