

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa
(County)

Located In: _____ Corner Code #/

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

94 JUL 22 AM 11:09

J. Roger Mallick
REGISTER OF DEEDS

1. Public Land Survey		T	44N	R	1W	M-8
1/4 Corner Common:		T	44N	R	1E	A-8
Section Corner		T	44N	R	1W	M-7
Common to :		T	44N	R	1E	A-7
2. Property Controlling	S	T		R		
in Section	S	T		R		
3. Miscellaneous	S	T		R		
Property in Sec.	S	T		R		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Keith R. Waters, in a field survey on OCTOBER 3, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M-8) From N. Hill L.L.S., 1991: Corner location established on line & midway between Section Corners.

1992: Neil Hill reset corner (L.7, P.362). East 75.50' Power Pole, West 78.48' Telephone Pole, S30E 115.45' 5" Poplar, N45E 106.10' Fence Post, North 2613.61' Section Corner, South 2613.61' Section Corner

(M-7) From 1980 ICRC, Liber 5, Page 002: Found 3/4" iron bar in monument box in centerline of M-129.

1992: Neil Hill found 3/4" iron and accepted (L.7, P.362). S73W 47.99' Chis "X" E. End Conc. Hdwl., N65W 48.02' Chis "X" E. End Conc. Hdwl., N65E 81.39' MDOT Tag PP PD4/20/15, S50E 68.72' MDOT Tag in Sign Post, South 2613.61' 1/4 Corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-8) Found corner and all accessories as recorded in Liber 7, Page 362 of the Chippewa County Records. Accepted corner position as found.

(M-7) Found corner and all accessories as recorded in Liber 7, Page 362 of the Chippewa County Records. Accepted corner position as found.

SURVEY & REMONUMENTATION

JUL 26 1994

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-8) 1/2" rod & cap #27447 in mon. box in line with fences East and West

(M-7) 3/4" iron in monument box at M-129 and 21 Mile Road.

WITNESSES

WITNESSES

East	75.50'	Power Pole
West	78.48'	Telephone Pole
S 30 E	115.45'	5" Poplar
N 45 E	106.10'	Fence Post
North	2613.61'	Section Corner
South	2613.61'	Section Corner

S 73 W	47.99	Chis "X" E. End Conc. Hdwl.
N 65 W	48.02'	Chis "X" E. End Conc. Hdwl.
N 65 E	81.39'	MDOT Tag PP PD4/20/15
S 50 E	68.72'	MDOT Tag in Sign Post
South	2613.61'	1/4 Corner

Signed by Keith R. Waters Date 7-22-94

Surveyor's Michigan License No. 33142

NOTE: Bearings are compass bearings corrected for declination. Distances are to a nail in side of witness objects unless noted.