

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Chippewa COUNTY


T 4N R 1W

DESCRIPTION OF CORNER 1/4 Cor. bet. Secs. 8-17

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 12/21/71

WITNESSES TO CORNER..... 8" Tamarack (1/4 S NBT) S55°E 16.9'



7" Jack Pine (1/4 S LBT) S24°W 23.1'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This 1/4 Cor. placed midway and on line bet. two Sec. Cors.

Found no evidence of original corner, but did find a wood post, 85.8' west of this corner, set by unknown persons. I did not accept this post as the corner location.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE

1/7/72

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing ✓

R 4047
Rev. 10/68