

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

CHIPPEWA CO.

2 CORNERS.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>XIX</u> S. R. <u>1</u> W.	<u>F-5</u>
2. PROPERTY CONTROLLING IN SECTION <u>16</u>	T. <u>44</u> N. <u>IX</u> S. R. <u>1</u> W.	<u>2</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-9, 1987, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- F-5 North 1/4 Corner of Section 16. O.B.T.'S: Fir 10", S70°W, 15 lks. & Fir 10", N44°E, 30 lks.
- 2 East 1/16 Corner of Section 16. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-5 Corner set M.P.O.L. between the N.W. and N.E. Corners of Section 16.
- 2 Corner set M.P.O.L. between North 1/4 Corner and N.E. Section Corner of Section 16.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
DNR Monuments set at both corners.

- |                            |                           |
|----------------------------|---------------------------|
| F-5 8" Aspen, N88°W, 9.95' | 2 10" Maple, N50°W, 28.9' |
| 8" Aspen, N47°W, 19.95'    | 14" W. Pine, N5°E, 14.2'  |
| 6" Aspen, N75°E, 18.8'     | 5" W. Pine, N66°E, 21.8'  |
| 6" Balsam, S44°E, 5.1'     | 3" Maple, East, 11.3'     |

SIGNED BY

Gerald L. Wiggins  
Gerald L. Wiggins

DATE

8-31-87

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

