

#29

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Chippewa

| | | |
|---------------------------------------|--------------------------|---------------|
| | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>44N</u> R <u>1W</u> | <u>E2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

Aug 21 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | 17 | 18 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
 (E2) Quarter corner common to Sections 4-5. Corner established in 1845 by James Mullett: "North between Sections 4&5...40.00 a Y. Pine 18 in. diam. for quarter section corner...80.19 Intersected N boundary..." No bearing trees noted in the original notes. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E2) Found no evidence of the position of the original corner tree. Found no evidence of subsequent monumentation or evidence of use. Reestablished the corner on a straight line between Closing corner 2619.10' north and Section corner 2606.72' south, the position being proportionate to the original record. At the position for the corner, I caused to be placed a 1"IDx36" iron pipe capped with a 4" diameter cast aluminum MDNR tablet appropriately stamped. Corner placed by T.Stark and D.Lampela, Newberry.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E2) Set 1" pipe with 4" MDNR cap.
 Blazed, scribed, and set measuring nails
 in the following:
 12" W. Pine N80E 13.95' "1/4S NBT"
 10" R. Pine S27E 5.75' "1/4S NBT"
 6" W. Pine S48E 10.2' "1/4S NBT"
 5" Maple North 12.15' "1/4S NBT"
 Placed a 3" squared and scribed cedar
 post adjacent. Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

8/22/96

Surveyor's Michigan License No.

33986