

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling In Section	S	8	T	44N	R	1W
	S	8	T	44N	R	1W
						1/64 C-E-SE
3. Miscellaneous Property in Sec.	S	8	T	44N	R	1W
	S	_____	T	_____	R	_____
						1/64 S-S 8-9

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

1/64 October 04, 1994

1/64 October 04, 1994

I, Stephan J. Szyszkoski, in a field survey on January 11, 1995, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(1-Sec. 8) West 1/16 corner between Sections 5-8. Corner not established in the original survey. Found no subsequent record.  
 (1/64 C-E-SE) 1/64 corner between 1/16 corners #13 and #14, Section 8. Corner not established in the original survey. Found no subsequent record.  
 (1/64 S-S 8-9) South South 1/64 corner between Sections 8 and 9 (being between the Section corner 8-9-16-17 and 1/16 corner #14 of Section 8). Corner not established in the original survey. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(1-Sec. 8) Found no evidence of prior monumentation at the corner position. Established the corner equidistant and on a straight line between section corner 1318.95' west and quarter corner 1318.95' east. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" diameter cast aluminum MDNR tablet, appropriately stamped.  
 (1/64 C-E-SE) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between 1/16 corners 667.45' east and west. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" diameter cast aluminum MDNR tablet, appropriately stamped.  
 (1/64 S-S 8-9) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Section corner 8-9-16-17 and the south 1/16 corner between sections 8-9, these corners being 651.69' south and north, respectively. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" diameter cast aluminum MDNR tablet, appropriately stamped.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(1) Set a 1" ID iron pipe with a 4" MDNR cap. Blazed, scribed, and set measuring nails with tags in the following: 6" J. Pine N10E 33.25' "N1/16 8T" 6" J. Pine S77E 16.85' "N1/16 8T" 6" J. Pine S42E 18.15' "N1/16 8T" 5" J. Pine S07W 10.1' "N1/16 8T" Set a 6" squared and scribed cedar post adjacent. Bearings are magnetic.	(1/64 C-E-SE) Set a 1" ID iron pipe with a 4" MDNR cap. Blazed, scribed, and set measuring nails with tags in the following: Clump 10" Oak N80W 24.25' "8T" 8" Balsam S05E 29.05' "8T" 8" Spruce S46E 55.7' "8T" 8" Clump Maple S20E 49.05' "8T" 2" Iron pipe S88E 29.0' NE corner of cabin S06W 55.25' NW corner of cabin S27W 59.8'. Bearings are magnetic.	(1/64 S-S 8-9) Set a 1" ID iron pipe with a 4" MDNR cap. Blazed, scribed, and set measuring nails with tags in the following: 8" Maple N10W 4.35' "8T" 3" Oak N50W 12.95' "8T" 4" Oak S85W 8.4' "8T" 3" Oak S01E 9.85' "8T" Placed a 5" squared cedar post adjacent. Bearings are magnetic.
---	--	--

Signed by Stephan J. Szyszkoski

Date 2-7-95

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3		7	8	9	10	11	12						
4													
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							



No. \_\_\_\_\_