

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
 Chippewa County Remonumentation Corner

For corners in

Chippewa County Located in: Corner Code #

1. Public Land Survey T44N R1W K-3
 T R
 T R
 T R
 T R
 T R

2. Property Controlling S T
 in Section S T
 3. Miscellaneous S T
 Property in Sec. S T

4. Lot No. , Recorded Plat
 5. Private Claims

**SURVEY &
 REMONUMENTATION**

FEB 23 2001

SECTION

\$2.00 M55R
 2 FEB 2001 3:51:16 PM Receipt #1103
 RECEIVED FOR RECORD
 CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK **11** PAGE **198**

Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on November 6, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-3 Corner Common to Sections 1, 2, 11 & 12, T44N, R1W.

1845 - Original corner established by James H. Mullett.
 Witnesses: Hemlock 16, N45°E 23 links - White Pine 30, S62°W 20 links.

Found no evidence of subsequent restoration of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


This corner is being reestablished as part of the Chippewa County Remonumentation Program. Found no evidence of the original corner. Reestablished corner by double proportionate measurement, using the closing section corner on the township line at K-1 to the north, the section corner at K-5 to the south, the section corner on the meridian at M-3 to the east, and the section corner at I-3 to the west. A squared wood post, which I believe was set by a local landowner or timber cruiser, bears S19°E 142.5 feet from the reestablished corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a 3/4" x 24" rebar with a stamped aluminum Chippewa County Remonumentation cap the corner location.

Witnesses:
 Nail and plastic witness tag #33142 in blazed 10" Hemlock, N04°W 21.12'
 Nail and plastic witness tag #33142 in blazed 10" Hemlock, S81°E 38.08'
 Nail and plastic witness tag #33142 in blazed 12" Maple, SOUTH 17.85'
 Nail and plastic witness tag #33142 in blazed 12" Balsam Fir, S57°W 34.38'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by Keith R. Waters

Date 12-29-00

Surveyor's Michigan License No. 33142