

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Chippewa County Remonumentation Corner

For corners in

Chippewa County Located in: Corner Code #

1. Public Land Survey T44N R1W L-11
T R
T R
T R

2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. , Recorded Plat

5. Private Claims

\$7.00 LAND CORNER

\$2.00 MSSR
2 FEB 2001 3:59:29 PM Receipt #1103
RECEIVED FOR RECORD
CHIPPewa COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

**SURVEY &
REMONUMENTATION**

BOOK 11 PAGE 211

FEB 23 2001

Register of Deeds Stamp & File Number

SECTION

I, Keith R. Waters, in a field survey on November 8, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

L-11 ¼ Corner Common to Sections 25 & 36, T44N, R1W.

- 1845 – Original corner established by James H. Mullett was an 8" Tamarack.
- 1908 – Chippewa County Surveyor Frederick H. Brown, RLS 944. Drawing of Section 25 shows the South ¼ corner midway between section corners 2638 feet east and west.
- 1911 – Chippewa County Surveyor Frederick H. Brown, RLS 944, Drawing of Section 36 shows the North ¼ corner midway between section corners 2637 feet east and west.
- 1985 – William L. Karr, P.S. 27450, LCRC Liber 6, page 301, Chippewa County corner records. Used north-south fence lines to reestablish corner in centerline of east-west road. Location matched a split between the north-east and northwest corners of Section 36. Witnesses:
½" x 18" Iron w/cap #27450 on fence line, Due North 29.47'
½" x 18" Iron w/cap #27450 on fence line, S03°W 41.71'
(No other ties available).



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program. Found a ½" iron with cap #27450 and the two witnesses as called for in the above mentioned 1985 LCRC. The distances to the section corners at K-11 and M-11 are 2637.12 feet and 2638.40, respectively, matching closely those as shown by County Surveyor Brown. Replaced the found ½" iron with a ¾" rebar and plastic Chippewa County Remonumentation cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a ¾" x 24" rebar with a plastic Chippewa County Remonumentation cap the corner location, which falls in the centerline of an east-west gravel road (23 Mile Road), on fence lines north and south.
Witnesses:
Nail and plastic witness tag #33142 in 22" Oak, N78°W 874.77'
Northeast corner of Concrete Barn Foundation, S88°W 1102.89'
½" Iron w/cap #27450 on Fence Line, N03°W 29.74'
½" Iron w/cap #27450 on Fence Line, S03°W 41.48'



Signed by Keith R. Waters

Date 12-29-00

Surveyor's Michigan License No. 33142