

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey

T 44N R 1W J8

T _____ R _____ _____

T _____ R _____ _____

T _____ R _____ _____

2. Property Controlling
in Section

S 21 T 44N R 1W 16

S _____ T _____ R _____ _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____ _____

S _____ T _____ R _____ _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

16 Jul 09 2003

J8 Jul 08 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (J8) Center of Section 23. Not established in the original survey.
- (16-Sec. 21) East 1/16 corner between Sections 21-28. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (J8) Established the corner at the intersection of straight lines connecting opposite Quarter corners, all of record. The corner established falls 3' East of and 10' South of the intersection of the centerlines of ditches South and West.
- (16-Sec. 21) Found and accepted a PK nail with a brass tag midway and on line between Section corner to the east and Quarter corner to the west. Replaced the PK nail with a monument as described below. The corner falls in the centerline of Hwy. M-48.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (J8) Set 1"IDx36" I. pipe with 4" alum. MDNR cap. Set measuring nails with plastic tags in: | (16) Set 1/2" dia. rebar with plastic cap "MICH DNR PS 33986". Blazed, scribed, and set measuring nails in: |
| 10" Tamarack S29E 82.8' | 10" Tamarack N70E 111.4' "E1/16 BT" |
| 20" Spruce S20E 99.05' | 6" Balsam S08W 60.6' do |
| 5" Willow N36W 19.8' | 6" Balsam S61W 104.95' do |
| Wooden fence post N12E 79.2' | 10" Spruce N46W 103.8' do |
| Bearings are magnetic. Distances are to nail with tag. | Bearings are magnetic. Distances are to nail with tag. |



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 7/29/03