

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S 14	T 44N R 1W	13
	S 23	T 44N R 1W	3
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

3 Jul 09 2003
 13 Jun 25 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (13-Sec. 14) Southeast 1/16 corner, Section 14. Not established in the original survey.
 (3-Sec. 23) North 1/16 corner between Sections 22 and 23. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(13-Sec. 14) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. From the corner thus established, a post in a fence line east bears 4 ft. South. The corner lies on the south side of a small waterflow running East and South with the corner at the bend.
 (3-Sec. 23) Established the corner midway and on a straight line between Section corner 1305.47' North and Quarter corner 1305.47' South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(13) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 5" Scotch Pine S30E 61.6' "SE1/16 BT" 6" Scotch Pine S55E 58.2' do 6" Tamarack N29E 29.0' do 12" Tamarack N52W 29.7' do Bearings are magnetic. Distances are to nail with tag.	(3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails with plastic tags in: 5" Aspen S85E 16.7' 6" Aspen N13E 25.7' 8" Aspen N69W 27.5' 8" Aspen S67W 33.8' The corner falls on the E. side of the shoulder of N-S road. Bearings are magnetic. Distances are to nail with tag.
---	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/29/03

For the Michigan Department of Natural Resources - Office of Land and Facilities