

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Chippewa
 (County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|-------------|--------------|---|------------|----------|
| 1. Public Land Survey | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | S <u>28</u> | T <u>44N</u> | R | <u>01W</u> | <u>1</u> |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

I, Stephan J. Szyszkoski, in a field survey on Nov 29, 20 06 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (1-Sec. 28) West 1/16 corner between Sections 21 and 28. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (1-Sec: 28) Established the corner midway and on the section line between Section corner 1312.78' west and Quarter corner 1312.78' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (1-Sec. 28) Set 1"ID I.pipe with plastic cap.
 Set measuring nails with MDNR tags in:
 7" Balsam S34W 72.13' blazed and scribed
 6" Balsam S09W 64.45' do
 6" Balsam S29E 80.5' do
 8" Aspen N18E 99.05' do
 Corner falls in E-W road.
 Bearings are magnetic. Distances are to nail with MDNR tag in side of tree.



1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Signed by Stephan J. Szyszkoski Date 9/11/07

Surveyor's Michigan License No. 33986