

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	S <u>29</u> T <u>44N</u> R <u>01W</u>	<u>12</u>
2. Property Controlling in Section	S <u>29</u> T <u>44N</u> R <u>01W</u>	<u>13</u>
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

I, Stephan J. Szyszkoski, in a field survey on Sept 26, 2006 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (12-Sec. 29) South 1/16 corner, Section 29. Not established in the original survey.
- (13-Sec. 29) Southeast 1/16 corner, Section 29. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (12-Sec. 29) Established the corner midway and on a straight line between Center of Section 1314.76' north and Quarter corner 1314.76' south.
- (13-Sec. 29) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |   |
|--|---|
| (12-Sec. 29) Set 1"IDx36" I.pipe with 4" aluminum MDNR cap. Set measuring nails with MDNR tags in: | (13-Sec. 29) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails with MDNR tags in: |
| 5" Balsam S40E 13.97' marked "S1/16 BT"  | 12" Maple S21W 16.13' mrkd "SE1/16 BT"  |
| 11" Balsam N47W 23.1' do   | 5" Balsam S33E 23.19' do  |
| 6" Balsam S29W 18.45' do   | 12" Maple N83E 28.85' do  |
| 8" Balsam S70W 17.32' do   | 10" Tamarack N02W 28.4' do  |
| Bearings are magnetic. Distances are to nail with tag in side of tree.                             | Bearings are magnetic. Distances are to nail with tag in side of tree.                          |

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by Stephan J. Szyszkoski



Date 9/11/07

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities