

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N.R. 6-7W


Mackinac COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 19, 30, 24 and 25.

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 3-19-63

WITNESSES TO CORNER..... 7" Cedar (S. 24 N.B.T.) N. 78° W., 10 Lks.



8" Cedar (S. 19 N.B.T.) N. 42° E., 29½ Lks.

8" Cedar (S. 30 N.B.T.) S. 62° E., 13 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced as set by Marcus Schaaf, Registered Land Surveyor. Found Schaafs' Post; a Tam. stump bottom in proper position; a green cedar marked and noted and tie-ins to his random lines as noted.

Corner found by Marcus Burnis, Forestry Aide.

Cor. lies in thick cedar swamp.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 10/11/63
REGISTERED LAND SURVEYOR