

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N.R. 6 W.


Chippewa - Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner between Sections 31-32 on South Boundary of Township.

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9-18-63

WITNESSES TO CORNER..... 12" Cedar (S. 31 N.B.T.) N. 38° W., 40 Lks.



CIRCLE CORNER REGISTERED

8" Hard Maple (S. 32 N.B.T.) N. 21° E., 37 Lks.

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was placed on line between Section Corners 1 mile East and 1 mile West and at Record distance from East.

Note: Closing Corner between Sections 5-6, T. 43 N., R. 6 W., lies 51 Links East of this Corner.

SURVEYOR'S SEAL

SIGNED Billy O. Buckles DATE 1/27/64
REGISTERED LAND SURVEYOR