

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 44 N.R. 6-7 W.


Chippewa-Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 18, 19, 13, 24

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9/24/63

WITNESSES TO CORNER..... 9" Hard Maple (S. 18 N.B.T.) N. 38° E. 23½ Lks.



11" Hard Maple (S. 19 N.B.T.) S. 16° E. 26½ Lks.

9" Hard Maple (S. 24 N.B.T.) West 31½ Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by single proportionate measure along township line from original corners 1 mile North and 1 mile South. Found a Cedar Post set by unknown persons 55 Lks. North and 60 Lks. East of corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 4/27/64  
REGISTERED LAND SURVEYOR