

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N.R. 6-7 W.


Chippewa-Mackinac COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 13-18

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9/24/63

WITNESSES TO CORNER..... 9" Cedar (1/4 S. N.B.T.) N. 69° E. 102 Lks.



8" Cedar (1/4 S. N.B.T.) S. 75° W. 156 Lks.

Corner lies on West edge of old Rail Road Grade.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by Single Proportionate Measure along township line from original corners 1/2-mile North and 1½ miles South.

Found a 24" W. Pine Stump scribed "1/4 S." bearing N. 65° E. 38½ Lks. from Corner. Marks are very old. Possibly a Railroad Survey.

SURVEYOR'S SEAL

SIGNED Billy O. Buckles DATE 1/27/64
REGISTERED LAND SURVEYOR