

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N.R. 6-7 W.

Chippewa-Mackinac COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 19-24

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap


DATE MONUMENT PLACED AND WITNESSED 9-24-63

WITNESSES TO CORNER..... 11" Cedar (1/4 S. N.B.T.) N. 68° E. 37 Lks.

7" Cedar (1/4 S. N.B.T.) S. 36° W. 35½ Lks.

10" Cedar (1/4 S. N.B.T.) N. 67° W. 30½ Lks.

AND squared and scribed 7" Cedar at Corner.



CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by single proportionate measure along Township line from corners 1/2-mile South and 1½ miles North. No evidence of original corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckles DATE 1/27/64
REGISTERED LAND SURVEYOR