

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 44 N.R. 6-7 W.


Chippewa-Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 30-31-25-36

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9-25-63

WITNESSES TO CORNER..... 5" Tamarack (S. 36 N.B.T.) S. 40° W. 133 Lks.



No other available.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by single proportionate measure along township line from Corners 1 mile North and 1 mile South.

Corner lies in open marsh.

SURVEYOR'S SEAL

SIGNED Billy O. Buckles DATE 1/27/64  
REGISTERED LAND SURVEYOR