

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N. R. 6 W


Chippewa COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 32 and 33

CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 10/18/60 Shown by Forester Halbach

WITNESSES TO CORNER.... 6" S. Maple (S 32 NBT) N 35° W 61 Links



5" S. Maple (S 33 NBT) N 38° E 36 1/2 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed 20 links west of closing corner for Sections 4 and 5, T 43 N, R 6 W, as recorded in field notes. Old wood post in proper place with another old down post.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE July 14, 1961
REGISTERED LAND SURVEYOR
Billy D. Buckler