

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Chippewa Co.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 N. 31/2 W. R. 6	M-12, E-11
2. PROPERTY CONTROLLING IN SECTION	T. 44 N. 31/2 W. R. 6	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-16-79, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- M-12 1/2 Cor. on East Side, Sec. 36, set by Wm. O. Burt, D.S. in 1840. Bearings were: Tamarack 5, N30°W, 17 Lks - cedar 4, S80°W, 17 Lks.
- E-11 Sec. Cor. 28-29-32-33, set by original survey in 1845. Bearings were: Hemlock 10, S47°W, 55 lks. & birch 20, S66°E, 48 lks.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-12 Found concrete monument with brass plate, set by General Land Office Survey. Corner is midway and on line bet. two section corners. Area is presently under water, no trees near, are suitable for witnesses.
- E-11 Restored corner at site of several cedar trees blazed as witnesses, at least 50 years ago. Found 12" cedar with face, indistinguishable crayon marks, 7.0' west of corner. This cedar has grown for 25 years after being blazed, is now down and badly rotted.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-12 Recording monument as found, no witnesses available.
- E-11 Placed 1" pipe w/4" alum. cap at corner. New bearings: 12" soft maple, S11°W, 41.3' - 12" maple, N15°W, 31.2' - 20" cedar, S43°E, 26.7'

SIGNED BY Billy D. Buckler DATE 3-17-80
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____