

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Chippewa Co. 3 Corners.

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|--|---|--|
| 1. PUBLIC LAND SURVEY _____ T. _____ | N. _____ S., R. _____ E. _____ W. _____ | _____ |
| 2. PROPERTY CONTROLLING IN SECTION <u>25</u> | T. <u>44</u> N. _____ S., R. <u>6</u> E. _____ W. _____ | <u>2-Sec.25 & 9-Sec.25</u> <u>16-Sec.25</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. _____ S., R. _____ E. _____ W. _____ | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-20, 21, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 2-Sec.25 East 1/16 Corner bet. Sec's. 24-25.
- 9-Sec.25 East 1/16 Corner of Section 25.
- 16-Sec.25 East 1/16 Corner bet. Sec's. 25-36.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 2-Sec.25 Buried 36" T-Iron 14.5' South of Hwy. Centerline. Corner placed on line bet. 1/4 corner to West and Sec. Cor. to East. Found 1" pipe, South, 12.3' from corner position.
- 9-Sec.25 Placed 1" pipe with 4" alum. cap at corner, midway bet. Sec. Center and East 1/4 Cor.
- 16-Sec.25 Established corner midway and on line bet. 1/4 cor. to West and Sec. Cor. to East. Placed 1" pipe with 4" alum. cap at corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 2-Sec.25 Bearings: 16" J. Pine, N51°W, 98.1' & 14" J. Pine, N35°E, 69.35' & Centerline of Hwy, North, 14.5'.
- 9-Sec.25 Bearings: 8" R. Maple, S41°E, 13.4' & 6" W. Birch, S41°W, 19.9' & Corner lies in South edge of E-W swale.
- 16-Sec.25 Bearings: 8" W. Pine, N40°E, 5.7' & 12" Hemlock, S83°W, 58.2' & 10" Cedar, S13°W, 56.5'.

SIGNED BY Billy D. Buckler DATE 5-4-81
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET