

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chippewa Co.

2 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. <u>6</u> E. <u>W.</u> S. R.	M-10
2. PROPERTY CONTROLLING IN SECTION <u>29</u>	T. <u>44</u> N. <u>6</u> E. <u>W.</u> S. R.	1-Sec. 29
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ E. _____ S. R.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-20&4-21, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- M-10 Quarter Corner, on East side of Section 25, set by original surveyor in 1840. Bearings were: Aspen 10", for Qr. Sec. Cor. and Aspen 6", N75°W, 17 lks.
- 1-Sec.29 West 1/16 Corner on line bet. Sections 20-29.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- M-10 Found 6" Concrete Monument with Brass Cap, set by U.S. General Land Office Survey in 1937. Found to be exactly midway and on line bet. two Sec. Corners.
- 1-Sec.29 Established corner midway bet. Sec. Cor. to West and 1/4 Cor. to East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-10 Re-witnessed Corner: New Bearings: 14" Spruce, S78°W, 17.5' & 8" Twin Spruce, S10°E, 26.1'.
- 1-Sec.29 Placed 1" pipe with 4" alum. cap at corner. Bearings: 8" Cedar, N74°W, 10.6' & 9" Cedar, S42°E, 15.5' & 7" Cedar, N64°E, 4.6'.

SIGNED BY Billy D. Buckler
Billy D. Buckler
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

DATE 5-4-81



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____