

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Chippewa Co. 4 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. R. <u>6</u> E. W.	<u>E-10, D-9, E-12, L-9</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-1, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- E-10 1/4 Cor. bet. Sec's. 28-29, set by original surveyor in 1845. Bearings were:
A B. Ash 10" for corner post.
- D-9 1/4 Cor. bet. Sec's. 20-29, set by original survey in 1845. Bearings were:
Cedar 4", S70°W, 13 lks. and Tam. 12", N4°W, 14 lks.
- E-12 1/4 Cor. bet. Sec's. 32-33, set by original survey in 1854. Bearings were:
Spruce 6", N20°W, 18 lks. and Spruce 5", N57°E, 23 lks.
- L-9 1/4 Cor. bet. Sec's. 24-25, set by original survey. Bearings were:
Spruce 11", S70°W, 16 lks. and Spruce 6", N57°E, 23 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-10 Re-established corner midway and on line bet. two section corners.
- D-9 Re-established corner midway and on line bet. two section corners.
- E-12 Re-established corner midway and on line bet. two section corners.
- L-9 Re-established corner midway and on line bet. two section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-10 Buried a 36" T-Iron in West edge of N-S Road. New Bearings:
10" Cedar, S60°E, 55.9' and 16" Cedar, S82°E, 57.9'.
- D-9 Placed 1" pipe with 4" alum. cap at corner. New Bearings: 6" Cedar, N85°W, 15.7' and
6" Cedar, S9°E, 10.7' and 6" Cedar, S49°E, 22.6'.
- E-12 Placed 1" pipe with 4" alum. cap at corner. New Bearings: 10" Twin Cedar, S32°W, 25.4' &
12" Cedar, S58°E, 24.3'.
- L-9 Placed a 36" T-Iron, 8' South of Center Co. Rd. H-40. New Bearings:
8" J. Pine, S19°E, 86.2' and 14" J. Pine, S21°W, 74.6'.

SIGNED BY

Billy D. Buckler
Billy D. Buckler

DATE 7-22-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

