

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chippewa Co.

3 Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 N. S. R. 6 W.	D-11, F-10
2. PROPERTY CONTROLLING IN SECTION 28	T. 44 N. S. R. 6 W.	5'
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-9 & 8-29, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

D-11 South 1/4 corner of section 29. Wood Post. OBT'S: A Tamarack 8" for 1/4 corner.

F-10 Center of section 28. Not prev. set.

5 North 1/16 corner of section 28. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

D-11 Corner set M.P.O.L. between section corners east and west.

F-10 Corner set at intersection on N-S and E-W 1/4 line section 28 by closed traverse.

5 Corner set M.P.O.L. between North 1/4 and Center Corner of section 28.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. Monuments set at all three corners. Bearings:

D-11 5" Tamarack, S70°W, 27.5' & 3" W. Pine, S80°W, 18.6' & 5" Tamarack, North, 6.4' & 6" Tamarack, N190°E, 63.4'.

F-10 10" Cedar, S69°E, 130.9' & Sq. Post Cedar, S150°E, 1.7' & Tag in Fence Post, N290°W, 118.6' & Tag in Fence Post, N100°W, 109.4'. Corner lies in south side of an old Beaver Meadow.

5 16" Aspen, N80°E, 30.4' & 8" Cedar, N650°E, 23.7' & 8" Cedar, S51°E, 45.1' & 8" Cedar, S520°W, 32.8'.

SIGNED BY

*Gerald L. Wiggins*  
Gerald L. Wiggins

DATE 9-5-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

